

**SURVEY &  
REMONUMENTATION**

Mar 15 95 04 1978

LIBER 15292 PG 366

MAY - 1 1995 LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

For corners in

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970 7.00 MISC RECORDING CHG - IN HOUSE

OAKLAND  
(County)

Located In: WATERFORD Corner Code #

- 1. Public Land Survey T 3 N R 9 E I-3  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

\$ 2.00 REMON CHG - IN HOUSE  
15 MAR 95 8:08 A.M. RECEIPT# 8B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-30-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3										●			
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, THOMAS M. SMITH, in a field survey on NOVEMBER 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 POST, G.L.O. 1817 BRASS PLATE 1963 1/2" IRON ROD L.C.R.C. L.14050 P. 015 KENNEDY, 1993

*Handwritten initials/signature*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 I FOUND A P.K. NAIL IN THE CENTER TURN LANE OF WALTON BLVD. I VERIFIED CORNER FROM THE KENNEDY WITNESSES.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 J-3: I REPLACED P.K. NAIL WITH A 5/8" ROD WITH CAP #31606 IN NEW MONUMENT BOX.  
 N 20 E. 87.37' to remon tag E. side 12" maple  
 N 10 W. 78.80' to remon tag W. side 16" maple.  
 N 40 W. 117.28' to S.E. foundation corner HSE. #3484  
 S 40 E. 86.21' to remon tag W. side 14" maple

THE SELECTED LOCATION IS ACCEPTED BY ME AND GENERALLY ACCEPTED BY PROFESSION SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by [Signature] Date DECEMBER 19, 1994

Surveyor's Michigan License No. 31606