

SURVEY & REMONUMENTATION

LIBER 15292 PG 362

MAR 15 95 04 1974

OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

For corners in
OAKLAND
(County)

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

Located In: WATERFORD Corner Code J-9

\$ 7.00 MISC RECORDING CHG - IN HOUSE
\$ 2.00 REMON CHG - IN HOUSE
15 MAR 95 8:07 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-30-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- | | | | | | | |
|------------------------------------|---|----------|---|----------|---|-----|
| 1. Public Land Survey | T | <u>3</u> | N | <u>9</u> | E | J-9 |
| | T | | R | | | |
| | T | | R | | | |
| | T | | R | | | |
| 2. Property Controlling in Section | S | | T | | R | |
| | S | | T | | R | |
| 3. Miscellaneous Property in Sec. | S | | T | | R | |
| | S | | T | | R | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, THOMAS M. SMITH, in a field survey on NOVEMBER 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST, G.L.O. 1" AXLE SHAFT
1817 ROAD COMMISSION
1963.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A IRON PIPE IN THE ASPHALT CENTERLINE OF CASS LAKE ROAD. I FOUND A IRON 33 FEET EAST OF THIS CORNER. THIS MATCHES THE ROAD COMMISSION TIE FROM 1963. MEASURED DIMENSIONS NORTH & SOUTH HIT CLOSELY WITH PLATTED DIMENSIONS.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9: I REPELACED THE PIPE WITH A 5/8" ROD WITH BRASS CAP IN A NEW MONUMENT BOX.
N 30 E. 87.57' to remon tag S.E. side 10" maple.
EAST 77.27' to remon tag S. side 10" maple.
S 30 E. 81.26' to remon tag W. side 14" maple.
WEST 93.98' to S.E. corner of school addition.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONA: SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by [Signature]

Date DECEMBER 19, 1994

Surveyor's Michigan License No. 31606

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

1888