

SURVEY &
REMONUMENTATION

LIBER 15292 PG 371

MAR 15 95 04 1983

OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OAKLAND

(County)

COMMISSION

Located in: WATERFORD

Corner Code #

- | | | | | | | | |
|------------------------------------|---|---|---|---|---|---|-----|
| 1. Public Land Survey | T | 3 | N | R | 9 | E | K-8 |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous Property in Sec. | S | | T | | R | | |
| | S | | T | | R | | |

\$ 7.00 MISC RECORDING CHG - IN HOUSE
\$ 2.00 REMON CHG - IN HOUSE
15 MAR 95 8:08 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-30-94
OAKLAND COUNTY REMONUMENTATION
PEFR GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, THOMAS M. SMITH, in a field survey on NOVEMBER 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|----------------------|---|---|
| POST, G.L.O.
1817 | 1/2" IRON IN MON. BOX
L.C.R.C.
L. 7899 P. 731
WILLIAMS, 1980 | 1/2" IRON IN MON BOX.
L.C.R.C.
L. 13427 P. 241
VAN HAVERMAAT. 1993 |
|----------------------|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A 1/2" ROD IN THE MONUMENT BOX AT THE INTERSECTION OF SCOTT LAKE & PONTIAC LAKE ROADS. I VERIFIED THE CORNER WITH THE L.C.R.C.'S RECORDED IN LIBER 7899, PAGE 731 & IN LIBER 13427, PAGE 241, ALSO MEASUREMENTS NORTH & SOUTH CLOSELY HIT PLATTED DIMENSIONS.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8: I REPLACED THE 1/2" IRON WITH A 5/8" ROD WITH A BRASS CAP #31606
N 45 W. 59.72' to remon tag W. side P.P.
N 60 E. 57.19' to remon tag N.W. side P.P.
S 45 E, 60.26' to remon tag S.W. side P.P.
S 50 W. 56.54' to remon tag S.E. side P.P.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by [Signature]

Date DECEMBER 19, 1994

Surveyor's Michigan License No. 31606