

SURVEY & REMONUMENTATION

LIBER 15292 PG 356

MAR 15 95 04 1968
OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OAKLAND (County)

COMMISSION

Located in: WATERFORD Corner Code #

\$ 7.00 MISC RECORDING CHG - IN HOUSE
\$ 2.00 REMON CHG - IN HOUSE
15 MAR 95 8:06 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-30-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3 N R 9 E L-5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, THOMAS M. SMITH, in a field survey on NOVEMBER 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST, G.L.O. 4" DIA. CONC. MON.
1817 L.C.R.C.
L. 8751 P. 220
HOBGOOD, 1984

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A CONCRETE MONUMENT AT A RIDGE LINE SOUTH OF SILVER LAKE IN A PARK AREA. I VERIFIED THIS CORNER FROM THE L.C.R.C IN LIBER 8751, PAGE 220 AND WITH ADJACENT LOT CORNERS SOUTHEASTERLY.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5: I PLACED A BRASS REMON. CAP #31606 ON THE CONC. MON.
NORTH 13.14' to remon tag E. side tree
N 20 E. 26.85' to remon tag S.E. side tree
EAST 20.35' to remon tag N. side tree
S 50 W. 117.24' to a capped iron

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by [Signature]

Date DECEMBER 19, 1994

Surveyor's Michigan License No. 31606

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

200
12