

**SURVEY & REMONUMENTATION**

LIBER **15292** PG **355**

MAR 15 95 04 1967  
OK - T. SMITH

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

7.00 MISC RECORDING CHG - IN HOUSE  
2.00 REMON CHG - IN HOUSE  
15 MAR 95 8:06 A.M. RECEIPT# 88  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

**OAKLAND**  
(County)

**COMMISSION**

Located In: **WATERFORD**

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>3</u> N R <u>9</u> E | <u>L-7</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-30-94  
OAKLAND COUNTY REMONUMENTATION PEER GROUP CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, THOMAS M. SMITH, in a field survey on NOVEMBER 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

POST G.L.O. 1817 CONCRETE MONUMENT  
L.C.R.C.  
L. 6831 P. 654  
JONES, 1974

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I FOUND A CONCRETE MONUMENT WITH A PIPE INSIDE THAT FITS THE DESCRIPTION OF THE MONUMENT SET FOR THE LaSALLE PARK SUB. I VERIFIED THE MONUMENT FROM THE L.C.R.C. RECORDED ABOVE AND WITH MEASURED DISTANCE WEST TO K-7.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-7: I PLACE A BRASS REMON. CAP #31606 ON THE EXISTING CONCRETE MONUMENT.  
N 40 E. 34.18' to remon tag W. side 10" elm  
S 20 E. 21.40' to remon tag W. side 10" elm  
S 30 W. 22.82' to remon tag N. side 12" oak  
S 80 W. 39.56' to remon tag S.E. side 6" wild cherry.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by [Signature]  
Surveyor's Michigan License No. \_\_\_\_\_

Date DECEMBER 19, 1994

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

*Handwritten initials/signature*

