

**SURVEY &
REMONUMENTATION**

LIBER **15292** PG **353**

MAR 15 95 04 1965

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

For corners in **COMMISSION**
OAKLAND
(County)

Filing Requirement of Act 74, Mich. P.A. 1970 \$ 7.00 MISC RECORDING CHG - IN HOUSE

Located In: WATERFORD Corner Code #/

\$ 2.00 REMON CHG - IN HOUSE
15 MAR 95 8:06 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

- | | | |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>3</u> N R <u>9</u> E | M-1 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-30-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, THOMAS M. SMITH, in a field survey on NOVEMBER 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

POST, G.L.O. NO L.C.R.C. RECORDED
1817

Handwritten initials/signature

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A 1/2" ROD AT MANN ROAD AND ROHR ROAD. I VERIFIED, ALONG WITH KEIFT ENGINEERING DOING WORK IN INDEPEDENCE TOWNSHIP THIS CORNER WITH MDOT RECORDS.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1: I REPLACED THE 1/2" ROD WITH A 5/8" ROD WITH A BRASS CAP #31606
S 35 E. 76.10' to remon tag W. side 16" pine.
EAST 22.94' to remon tag N. side 40" oak.
NELY 19.31' to mosteasterly S.E. corner guardrail post.
N 65 W. 42.40' to remon tag S. side 8" hickory.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by [Signature] Date DECEMBER 19, 1994
Surveyor's Michigan License No. 31606