

MAY 24 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

59630

SECTION

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Waterford Township	
1. Public Land Survey	T <u>3N</u> R <u>9E</u>	<u>M-2</u>
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 21146 PAGE 78
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/29/2000 10:58:27 A.M. RECEIPT# 165
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF I

RECEIVED ON: 11-24-99 512
OAKLAND COUNTY REMONUMENTATION
WORK GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on April 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	13	17	18	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There is one LCRC recorded at Oakland County; Hart 1995.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" capped rod #33136 at this location. This corner was set by Timothy J. Hart, Land Surveyor No. 33136, March 8, 1995 as recorded in LCRC L15298 P255. Validated the location of this iron with monumentation found in Whispering Oaks Subdivision. A-2 of Pontiac Township is 161.21' north of M-2 and on the township line between M-2 and M-1.

Recovered Witnesses:


- N 32°49'3"E 11.274' found PK nail in northwest side of 6" Pine.
- S 18°46'24"E 7.56' found PK nail in east side 12" Hickory.
- N 26°29'20"W 14.06' found PK nail in east side 12" Twin Oak.
- N 14°23'24"W 25.97' found PK nail southwest face twin 24" Oak.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- N 32°49'32"E 11.274' set Mag nail in northwest side 6" Pine.
- S 18°46'24"E 7.56' set Mag nail in east side 12" Hickory.
- N 26°29'20"W 14.06' set Mag nail with washer in east side 12" Twin Oak.
- N 14°23'24"W 25.97' set Mag nail with washer southwest side 24" Oak.
- N 02°39'21"W 161.21' concrete monument with brass cap stamped #21270.



Signed by Joseph C. Kapelczak Date 12/22/99

Surveyor's Michigan License No. 24598