

MAY 24 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

59632

For corners in

Oakland (county)	Located In:	Corner Code #
	Waterford Township	
1. Public Land Survey	T <u>3</u> N	R <u>9</u> E
	T_____R_____	M-8
	T_____R_____	
	T_____R_____	
	T_____R_____	
2. Property Controlling in Section	S_____T_____	R_____
	S_____T_____	R_____
3. Miscellaneous Property in Sec.	S_____T_____	R_____
	S_____T_____	R_____

LIBER 21146 PAGE 82
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/29/2000 10:58:27 A.M. RECEIPT# 16518
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Comply with
ACT 365, P.A. 1990

APPROVED ON: 11-24-99 512
OAKLAND COUNTY REMONUMENTATION
FILE GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on April 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.

There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a brass disc on a monument in monument box located in the parking lot south of the Oakland County Circuit Court. A-8 of Pontiac Township is 7.14' north of M-8 and on the Township Line. This corner was validated with recorded distances from Fred Soll's Pontiac Hospital Survey of 1926.

Recovered Witnesses:

- N 26°W 55.010' concrete nail south edge top of concrete light pole base.
- S 37°E 104.086' concrete nail in edge top of concrete light pole base.
- S 58°W 132.826' concrete nail north edge top of concrete light pole base.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Recovered brass disc in monument box.

Set Witnesses:

- N 26°W 55.010' concrete nail south edge top of concrete light pole base.
- S 37°E 104.086' concrete nail in edge top of concrete light pole base.
- S 58°W 132.826' concrete nail north edge top of concrete light pole base.
- N 55° 79.76' Set Mag nail with tag southeast face 6" Crabapple.
- N 02°07'37"W 7.14' A-8 Pontiac Township.



Signed by Joseph C. Kapelczak

Date 12/22/99

Surveyor's Michigan License No. 24598

2p
n