

LAND CORNER RECORDATION CERTIFICATE 31105
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Oakland
(County)

Located in: Pontiac
Twp. Corner Code #

LIBER 21052 PAGE 157
\$71.00 MISC RECORDING
\$21.00 REMONUMENTATION
02/01/2000 09:59:02 A.M. RECEIPT# 7944
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

1. Public Land Survey

T 3NR 10E A-12
T R _____
T R _____
T R _____

2. Property Controlling
in Section

S T R _____
S T R _____
S T R _____

3. Miscellaneous
Property in Sec.

S T R _____
S T R _____
SECTION

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 11-29-99 *JL*
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

November 23 99

I, Raymond J. McCoy, a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	13	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

Not an Original GLO corner.
There are No LCRC's recorded for this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner was established on line between A-13 and A-11 and equal distance.

State Plane Coordinates N 412003.6271
E 13403618.0617

lp
R

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set a 5/8"x24" iron rod with a 2" diameter brass disk stamped Oakland County Remonumentation P.S. #21270 in a New Monument Box.

Witnesses:
N 42° E, 70.25', Set OCRT in Southeast face of Power Pole
S 80° E, 109.45', Set OCRT in West face of Power Pole
S 17° W, 132.26', Set OCRT in Southeast face of Power Pole
N 22° W, 137.27', Top center of Hydrant

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Raymond J. McCoy
Surveyor's Michigan License No. 21270

Date Dec. 28, 99