

LAND CORNER RECORDATION CERTIFICATE 71711  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland  
 (County)

Located in Pontiac Corner Code #  
Twp.

\$7.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 03/03/1999 03:32:14 P.M. RECEIPT# 4986  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

1. Public Land Survey

T 3N R 10E G-5

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

SECTION

Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 1-20-99 JS  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Raymond J. McCoy, in a field survey on Feb. 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 1817 G.L.O. Wampler D.S. Set Post

- 1980 by Roger Moore, found two nails in pav. being 3.04' apart, both recorded as G-5. No witnesses were recovered.
- 1987 by Grant Ward, found P.K. nail as was previously recorded by Roger Moore. No witnesses were recovered.
- \* 1996 by Tim Hart, found iron in monument box being the Easterly Nail in the afore mentioned L.C.R.C.'s. All witnesses were recovered.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 I found a  $\frac{1}{2}$ " iron rod in a mon. box, centerline of Walton Blvd. and 7' West of the centerline of Arlene St., being the Easterly nail as recorded in L.C.R.C. #1&2 above.  
 Validated corner by monumentation recovered in "Chief Pontiac Farms", and all the witnesses recovered in L.C.R.C. #3 above.


State Plane Coordinate N 431110.5964  
E 13417986.7430

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Replaced found  $\frac{1}{2}$ " iron rod in mon. box with a  $\frac{5}{8}$ "x24" iron rod w/2" dia. brass disk stamped "Oakland County Remonumentation P.S. #21270."

- Witnesses:
- N25°E 68.51' Set O.C.R.T. #21270 in W face of P.P.
  - S78°E 234.63' Set O.C.R.T. #21270 in N face of P.P.
  - S30°E 65.15' Set O.C.R.T. #21270 in W face of P.P.
  - S71°W 197.50' Set O.C.R.T. #21270 in NW face of P.P.

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Raymond J. McCoy  
 Surveyor's Michigan License No. 21270



Date Feb 7 1999