

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 31113

For corners in

Oakland

(County)

Pontiac Twp.

Located in:

Corner Code #

LIBER 21052 PAGE 165
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/01/2000 09:59:02 A.M. RECEIPT# 7944
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

1. Public Land Survey

T 3N R 10E G-11

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

SURVEY & REMONUMENTATION

MAR 21 2000

SECTION

4. Lot No. , Recorded Plat

5. Private Claims

Raymond J. McCoy

July 23, 1999

I, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-K and rows 1-13. A dot is marked at the intersection of column G and row 11.

A. Description of original monument and accessories and/or subsequent restoration:

1817- Post, GLO

There is one LCRC recorded.

1) 1990- Ward, L. 11318, Pg. 57, all witness remain and verified.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" brass disk in Monument Box, centerline of Auburn & Martin Luther King Jr. Blvd's. Corner was validated by monumentation found in "CITIZENS Dev. Co." plat and in "HOMESTEAD PARK", more particularly fitting R/W distances and a measured distance from the found monument at Marshall & Auburn Road, East to the Section line(252.69(r), 252.47(M)).

State Plane Coordinates N 415458.4282
E 13418747.4677

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 5/8"x24" iron rod with a 2" diameter brass disk stamped Oakland County Remonumentation P.S. #21270 on top of the existing brass monument and filled with cement.



Signed by [Signature]
Surveyor's Michigan License No. 21270

Date November 23, 1999