

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

54460

For corners in

OAKLAND
(County)

Located in: PONTIAC Corner Code # G-12
TWP.

LIBER 21128 PAGE 353
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/23/2000 01:11:06 P.M. RECEIPT# 15051
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 9-15-99 *JR*
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

1. Public Land Survey

T 3 N R 10 E G-12

T R

T R

T R

2. Property Controlling
in Section

S T R RE TATION

3. Miscellaneous
Property in Sec.

S T R MAR 21 2000

SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

I, Raymond J McCoy, in a field survey on Dec 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1817 G. L.O. Wampler D.S. Set Post. The Corner has been perpetuated by monumentation for adjacent Subdivision.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod incased in concrete in Monument Box validated its Location by monumentation in "L.I. CARRIER MURPHY PARKSUBDIVISION"
Recorded in L.24 Pg. 29, O.C.R.D.

State Plane Coordinate

N 412548.38810

E 13418886.6096

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set a 2" Dia brass disk stamped Oakland County Remonumentation #21270 On Ironin Mon. Box.


Witnesses;

N. 70° W. 38.61 Chisled X on S.E. Bolt for L.P.

N. 20° E 110.73 Chisled X on S.W. Bolt For L.P.

S83° E 74.46 Chisled X on N.W. Bolt of L.P.

S. 17° W 113.23 Set O.C.R.T. in S.E. face of P.P.



Signed by

Raymond J. McCoy

Date

Feb. 7, 00

Surveyor's Michigan License No. 21270