

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 31119

For corners in

Oakland

(County)

Pontiac Twp.

Located in:

Corner Code #

LIBER 21052 PAGE 171

\$9.00 MISC RECORDING

\$2.00 REMONUMENTATION

02/01/2000 09:59:04 A.M. RECEIPT# 7944

PAID RECORDED - OAKLAND COUNTY

G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

1. Public Land Survey

T3N R 10E I-10

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

QUINCY & REFINEMENTATION

MAR 21 2000

Compliance with ACT 31, P.A. 1990

10-13-95 JIL

OAKLAND COUNTY REMONUMENTATION

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims SECTION

Raymond J. McCoy

September 23 99

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K
1											
2	6		5		4		3		2		
3											
4	7		8		9		10		11		1
5											
6	18		17		16		15		14		1
7											
8	19		20		21		22		23		2
9											
10	30		29		28		27		26		2
11											
12	31		32		33		34		35		3
13											

A. Description of original monument and accessories and/or subsequent restoration:

1817 Post GLO

There is one LCRC recorded for this corner.

1) 1993-Stonerock, L. 13326, Pg. 188, Set Magnet, 4 remaining witnesses

2p  
h

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 3/4" magnet in the concrete pavement of South lane of Westbound M-59 Highway, 20'+/- East of Opdyke Road Bridge and 39'+/- North of a concrete barrier. Corner was validated by measuring closely to the sidwell distance(Tax Map) to the South. Set 2 reference Monuments, one 100.00 feet North and one 130.00 South of the actual corner.

State Plane Coordinates N 418138.2751  
 (Actual Corner) E 13423883.2701

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SEE BACK FOR WITNESSES: Set 2 REFERENCE MONUMENTS, ONE 100.00 FEET NORTH, ONE 130.00 SOUTH OF ACTUAL CORNER ON THE SECTION LINE.



Signed by

*Raymond J. McCoy*  
 \_\_\_\_\_

Date

1-5-00

Surveyor's Michigan License No.

21270

ACTU... ORNER LOCA... N FOR I-10

~~NORTH-REFERENCE-MONUMENT~~ LIBER 21052 172

WITNESSES:

South, 38.85' Set OCRT on Top of Barrier Wall of M-59 Highway  
S 32° W, 44.72' Found Nail & Washer Top of Bridge Support Wall  
N 31° W, 51.25' Found Nail & Washer Top of Bridge Support Wall  
North, 44.06 Set OCRT Top of Guardrail post.

SOUTH REFERENCE MONUMENT

WITNESSES:

N 17° W, 96.76 Found Nail & Washer Top of Bridge Support Wall  
N 44° E, 125.27 Set chiseled "x" on Top of concrete barrier wall  
N 3° W, 91.18 Set OCRT in Top of concrete barrier wall  
S 1° W, 110.90' Set OCRT in E. face of Power Pole  
N 2° W, 130.00 to I-10

NORTH REFERENCE MONUMENT

WITNESSES:

N 30° W, 17.33' Set OCRT in SW face of Power Pole  
S 5° E, 56.03' Set OCRT in Top of Guardrail Post  
S 35° E, 170.54' Set chiseled "x" on Top of concrete barrier wall  
S 2° E, 138.82' Set OCRT in Top concrete barrier wall  
S 2° E, 100.00 to I-10

SURVEY &  
RECORDS

MAR 21 2000

SECTION