

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Oakland
(County)

Pontiac
Located in: Twp. Corner Code #

31129

1. Public Land Survey

T3N R 10E L-7

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R
S T R

LIBER 21052 PAGE 181
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/01/2000 09:59:20 A.M. RECEIPT# 7944
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 306, P.A. 1999

APPROVED ON: 9-22-99 JLR
OAKLAND COUNTY REGISTER OF DEEDS
REGISTER OF DEEDS

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____ SECTION _____

Raymond J. McCoy, in a field survey on September 7, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K
1											
2		6		5		4		3		2	
3											
4		7		8		9		10		11	
5											
6		18		17		16		15		14	
7											
8		19		20		21		22		23	
9											
10		30		29		28		27		26	
11											
12		31		32		33		34		35	
13											


A. Description of original monument and accessories and/or subsequent restoration:

1817 Post, GLO

There are 2 LCRC's recorded for this corner.

1) 1991-Kohn, L. 11750, Pg. 899, Set corner.

2) 1991-DeDecker, L.12014, Pg747, Found 1/2" rod cap #26459.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod w/cap #26459 in Woods, 550'+/- South of the centerline of Cross Creek Drive, west of Squirrel Road. Validated corner by the witnesses in the above LCRC's and by matching 1/2 mile distance to the East and matching very closely to the recorded angle formed at K-7, with K-6 & L-7.

State Plane CoordinatesN 426524.8594
E 13431773.1838

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a concrete monument consisting of a 1/2" iron rod 36" long fully encased in a 4" diameter concrete cylinder with a 2" diameter brass disk stamped Oakland County Remonumentation P.S. #21270.

Witnesses:

N 85° W, 10.53', Set OCRT in N face of 10" Poplar

N 20° W, 13.48', Set OCRT in NE face of 14" poplar

N 03° E, 7.02', set OCRT in E. face of 12" Poplar

S 10° E, 16.71', Set OCRT in W. face of 10" Poplar.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Raymond J. McCoy
Surveyor's Michigan License No. 21270

Date 1-5-00