

**SURVEY &
REMONUMENTATION**

LIBER 14992mc085

94 254968

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**
OAKLAND
(County)

Located In: AVON
TOWNSHIP Corner Code -#

- | | | |
|---------------------------------------|------------------------------|-------------|
| 1. Public Land Survey | T- <u>3-N</u> R- <u>11-E</u> | <u>G-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

OK - T. SMITH

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 1-26-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, DAVID PAWLACZYK, in a field survey on 12-1-30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

*POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
N. 35° E. 11 LINKS 12" WHITE OAK
S. 23° W. 38 LINKS 12" WHITE OAK*

David Pawlaczyk

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

*FOUND 1/2" RE-ROD IN MONUMENT BOX
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 7149 PAGE 456
LIBER 12585 PAGE 328*

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
22 SEP 94 8:41 A.M. RECEIPT# 33B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

*REPLACED THE 1/2" RE-ROD WITH P. A. 345 BRASS
CAP STAMPED # 17632 ON 3/4" X 24" IRON ROD.
ACCESSORIES ESTABLISHED
N. 60° E., 83.29' WITNESS TAG ON SOUTH FACE UTILITY POLE
S. 80° E., 59.55' CUT CROSS NORTH RIM GATE VALVE & WELL
S. 60° W., 61.71' WITNESS TAG ON NORTH FACE 16" COTTON WOOD
N. 80° W. 42.97 WITNESS TAG ON SOUTH FACE 8" MAPLE*

Signed by *David Pawlaczyk*

Date 1-11-94

Surveyor's Michigan License No. 17632

