

**SURVEY &  
REMONUMENTATION**

**LIBER 14992 PG 086**

**94 254969**

**MAY - 1 1995**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**  
OAKLAND  
(County)

Located In: AVON  
TOWNSHIP Corner Code ##

- |                                    |                            |             |
|------------------------------------|----------------------------|-------------|
| 1. Public Land Survey              | T <u>3-N</u> R <u>11-E</u> | <u>G-11</u> |
|                                    | T _____ R _____            | _____       |
|                                    | T _____ R _____            | _____       |
|                                    | T _____ R _____            | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____    | _____       |
|                                    | S _____ T _____ R _____    | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____    | _____       |
|                                    | S _____ T _____ R _____    | _____       |

**OK - T. SMITH**

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 1-26-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID PAWLACZYK, in a field survey on 12, 1-30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented; recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

*POST WAS SET PER GOVERNMENT LAND OFFICE NOTES  
N. 32° W. 102 LINKS 50" WHITE OAK  
S. 85° E. 104 LINKS 30" WHITE OAK*

*2500  
7.00*

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

*FOUND 1/2" RE-ROD IN ASPHALT ROAD  
PREVIOUS LAND CORNER RECORDATION CERTIFICATES  
LIBER 9207, PAGE 383  
LIBER 11538, PAGE 461  
LIBER 12585, PAGE 328*

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
22 SEP 94 8:41 A.M. RECEIPT# 33B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

*REPLACED THE 1/2" RE-ROD WITH P. A. 345 BRASS  
CAP STAMPED # 17632 ON 3/4" X 24" IRON ROD.  
ACCESSORIES ESTABLISHED  
N. 60° E., 60.05' WITNESS TAG ON NORTHWEST FACE UTILITY POLE  
S. 45° E., 74.05' WITNESS TAG ON SOUTHWEST FACE UTILITY POLE  
S. 70° W., 79.88' WITNESS TAG ON NORTH FACE UTILITY POLE  
N. 70° W., 88.02' WITNESS TAG ON NORTHEAST FACE UTILITY POLE*

Signed by [Signature]  
Surveyor's Michigan License No. 17632

Date 1-11-94

