

**SURVEY &  
REMONUMENTATION**

LIBER **14992** PG **089**

**94 254972**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OAKLAND  
(County)

Located In: AVON Corner Code ##  
TOWNSHIP

- |                                    |                              |             |
|------------------------------------|------------------------------|-------------|
| 1. Public Land Survey              | T- <u>3-N</u> R- <u>11-E</u> | <u>H-11</u> |
|                                    | T _____ R _____              | _____       |
|                                    | T _____ R _____              | _____       |
|                                    | T _____ R _____              | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____      | _____       |
|                                    | S _____ T _____ R _____      | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____      | _____       |
|                                    | S _____ T _____ R _____      | _____       |

OK - T. SMITH

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 1-26-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID PAWLACZYK, in a field survey on DECEMBER 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES  
S. 59° E. 15 LINKS 12" LYNN  
N. 43° W. 60 LINKS 15" BLACK OAK

*DAVID PAWLACZYK*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PK NAIL IN E CRACK JOINT  
PREVIOUS LAND CORNER RECORDATION CERTIFICATES  
LIBER 12585 PAGE 328

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
22 SEP 94 8:41 A.M. RECEIPT# 338  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE PK NAIL WITH P. A. 345 BRASS  
CAP STAMPED # 17632 ON 3/4" x 24" IRON ROD  
ACCESSORIES ESTABLISHED  
N. 45° E., 117.09' CUT CROSS NORTH RIM SANITARY MANHOLE  
S. 45° E., 159.04' WITNESS TAG ON WEST FACE UTILITY POLE  
S. 5° W., 63.45' WITNESS TAG ON EAST FACE UTILITY POLE  
N. 60° W., 139.15' WITNESS TAG ON NORTHEAST FACE UTILITY POLE

Signed by DAVID PAWLACZYK

Date 1-11-94

Surveyor's Michigan License No. 17632

