

**SURVEY &
REMONUMENTATION**

LIBER **14992** PG **091**

94 **254974**

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in **COMMISSION**

OAKLAND
(County)

Located in: AVON
TOWNSHIP Corner Code #

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
22 SEP 94 8:42 A.M. RECEIPT# 338
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with
ACT 345, P.A. 1990

APPROVED ON: 1-12-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- | | | |
|---------------------------------------|------------------------------|-------------|
| 1. Public Land Survey | T- <u>3-N</u> R- <u>11-E</u> | <u>H-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID PAWLACZYK, in a field survey on DECEMBER 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
N. 17° W. 23 LINKS 19" WHITE OAK
S. 44° E. 5 LINKS 38" WHITE OAK

Handwritten signature/initials

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD IN ASPHALT PAVEMENT
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 7522 PAGE 273
LIBER 8075 PAGE 758

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P.A. 345 BRASS
CAP STAMPED # 17632 ON 3/4" X 24" IRON ROD
ACCESSORIES ESTABLISHED

DUE NORTH, 17.42' WITNESS TAG ON EAST FACE UTILITY POLE
N. 80° E., 78.12' WITNESS TAG ON SOUTH FACE UTILITY POLE
N. 80° W., 79.75' WITNESS TAG ON SOUTH FACE UTILITY POLE
N. 40° W., 53.97' WITNESS TAG ON SOUTHWEST FACE 20" MAPLE

Signed by [Signature]

Date 1-11-94

Surveyor's Michigan License No. 17632

