

SURVEY & REMONUMENTATION

LIBER 14992 PC 093

94 254976

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

For corners in

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

OAKLAND (County) Located In: AVON TOWNSHIP Corner Code: #

- 1. Public Land Survey T-3-N R-11-E 1-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 22 SEP 94 8:42 A.M. RECEIPT# 338
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
 Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 1-12-94
 OAKLAND COUNTY REMONUMENTATION
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, DAVID PAWLACZYK, in a field survey on DECEMBER 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
 N. 86° W. 17 LINKS 28" WHITE OAK
 S. 73° W. 61 LINKS 25" WHITE OAK

Handwritten signature/initials

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD IN MONUMENT BOX
 PREVIOUS LAND CORNER RECORDATION CERTIFICATES
 LIBER 6373 PAGE 872
 LIBER 10279 PAGE 726

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P.A. 345 BRASS
 CAP STAMPED # 17632 ON 3/4" X 24" IRON ROD
 ACCESSORIES ESTABLISHED
 N. 45° E., 67.63' WITNESS TAG ON NORTHWEST FACE UTILITY POLE
 DUE EAST, 56.21' WITNESS TAG ON NORTH FACE UTILITY POLE
 S. 80° W., 93.95' NORTHEAST CORNER BRICK PILLAR NORTH END BRICK WALL
 N. 15° W., 279.11' @ TOP NUT OF FIRE HYDRANT

Signed by *[Signature]*

Date 1-11-94

Surveyor's Michigan License No. 17632

