

SURVEY & REMONUMENTATION

LIBER **14992** PG **094**

94 254977

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

OAKLAND
(County)

Located In: AVON
TOWNSHIP

Corner Code #

OK - T. SMITH

- | | | |
|------------------------------------|------------------------------|------------|
| 1. Public Land Survey | T- <u>3-N</u> R- <u>11-E</u> | <u>I-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
22 SEP 94 8:42 A.M. RECEIPT# 338
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with
ACT 345, P.A. 1990

APPROVED ON: 1-12-94
Register of Deeds Stamp # File Number
PEER GROUP COMMITTEE

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID PAWLACZYK, in a field survey on DECEMBER 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
N. 76° W. 11 LINKS 21" RED OAK
N. 27° E. 23 LINKS 8" ASH

Handwritten note:
700
200
1/2

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD IN MONUMENT BOX
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 5949 PAGE 72
LIBER 6260 PAGE 660
LIBER 7034 PAGE 568

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P.A. 345 BRASS
CAP STAMPED # 17632 ON 3/4" X 24" IRON ROD
ACCESSORIES ESTABLISHED
N. 60° E., 72.19' SOUTHWEST CORNER BLOCK BUILDING
S. 45° E., 92.57' WITNESS TAG ON NORTH FACE UTILITY POLE
S. 45° W., 186.38' NORTHEAST CORNER BRICK GAS STATION
N. 70° W., 85.51' WITNESS TAG ON SOUTH FACE UTILITY POLE

Signed by [Signature]

Date 1-11-94

Surveyor's Michigan License No. 17632

