

**SURVEY &
REMONUMENTATION**

LIBER **14992** PC **095**

94 254978

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

For corners in

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

OAKLAND
(County)

Located In: AVON
TOWNSHIP Corner Code #

- | | | |
|------------------------------------|------------------------------|-------------|
| 1. Public Land Survey | T- <u>3-N</u> R- <u>11-E</u> | <u>I-10</u> |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
22 SEP 94 8:43 A.M. RECEIPT# 338
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with
ACT 345, P.A. 1999

APPROVED ON: 1-12-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID PAWLACZYK, in a field survey on DECEMBER 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
S. 73° E, 12 LINKS 17" LYNN
N. 39° E, 23 LINKS 14" HICKORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2" BAR IN MONUMENT BOX
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 5840 PAGE 373
LIBER 7149 PAGE 456

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 2" BAR WITH P.A. 345 BRASS
CAP STAMPED # 17632 ON 3/4" X 24" IRON ROD
ACCESSORIES ESTABLISHED

N. 40° E., 159.00' WITNESS TAG ON NORTHWEST FACE UTILITY POLE
S. 45° E., 121.11' WITNESS TAG ON SOUTHWEST FACE UTILITY POLE
S. 45° W., 92.00' WITNESS TAG ON SOUTHEAST FACE TWIN 6" OAK
N. 80° W., 15.46' & TOP NUT OF FIRE HYDRANT

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

Handwritten: done 1/11/94
File

Signed by [Signature]

Date 1-11-94

Surveyor's Michigan License No. 17632

