

MAY 16 1996

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corner **COMMISSION**  
**OAKLAND**  
(County)

Located in: **AVON TOWNSHIP** Corner Code #

- 1. Public Land Survey T-3-N-R-11-E J-7
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Compliance with ACT 345, P.A. 1990  
APPROVED ON: 12-5-94  
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, DAVID PAWLACZYK, in a field survey on DECEMBER 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES  
S. 67° E. 80 LINKS 6" WHITE OAK  
N. 26° W. 46 LINKS 40" WHITE OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON BAR IN MONUMENT BOX  
PREVIOUS LAND CORNER RECORDATION CERTIFICATES  
LIBER 6373 PAGE 872  
LIBER 7769 PAGE 514  
LIBER 9923 PAGE 607  
LIBER 11622 PAGE 376

*7.00 fee  
2.00 file*

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
27 OCT 94 2:08 P.M. RECEIPT# 1738  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1" IRON BAR WITH P.A. 345 BRASS  
CAP STAMPED #17632 ON 3/4" X 24" IRON ROD  
ACCESSORIES ESTABLISHED  
DUE NORTH, 23.69' WITNESS TAG ON WEST FACE UTILITY POLE  
S. 15° E., 104.74' WITNESS TAG ON WEST FACE 14" PINE  
DUE SOUTH, 77.38' WITNESS TAG ON UTILITY POLE  
S. 50° W., 95.65' @ TOP NUT OF FIRE HYDRANT

Signed by [Signature]

Date 11-3-94

Surveyor's Michigan License No. 17632

