

**SURVEY &
REMONUMENTATION**

LIBER 14992 p. 100

94 254983

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

OAKLAND
(County)

COMMISSION

Located In: AVON Corner Code #
TOWNSHIP

OK - T. SMITH

- | | | | |
|------------------------------------|-------|--------|------|
| 1. Public Land Survey | T-3-N | R-11-E | J-13 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
22 SEP 94 8:43 A.M. RECEIPT# 33B
PAID RECORDED - OAKLAND COUNTY
LYNN D. REGISTER OF DEEDS
Compliance with Act 74, P.A. 1970

APPROVED ON: 1-12-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID PAWLACZYK, in a field survey on DECEMBER 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

*POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
N.34°W. 28 LINKS 16" WALNUT
S.05°W. 20 LINKS 11" BEECH*

*Boyd
D. Smith
1/11/94*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

*FOUND 1" IRON BAR IN ASPHALT PAVEMENT
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 6704 PAGE 351
LIBER 11062 PAGE 228
LIBER 13157 PAGE 563*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

*REPLACED THE 1" IRON BAR WITH P. A. 345 BRASS
CAP STAMPED #17632 ON 3/4" X 24" IRON ROD
ACCESSORIES ESTABLISHED
N. 10° E., 26.70' @ TOP NUT OF FIRE HYDRANT
N. 40° E., 34.54' WITNESS TAG ON EAST FACE UTILITY POLE
S. 45° E., 94.90' WITNESS TAG ON NORTHEAST FACE UTILITY POLE
S. 10° W., 43.41' @ TOP NUT OF FIRE HYDRANT*

Signed by David Pawlaczyk

Date 1-11-94

Surveyor's Michigan License No. 17632

