

SURVEY & REMONUMENTATION

94 254984

LIBER 14992 P. 101

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

OAKLAND
 (County)

Located In: AVON Corner Code #
TOWNSHIP

- 1. Public Land Survey T-3-N R-11-E K-7
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 22 SEP 94 8:43 A.M. RECEIPT# 33B
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
 Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 1-12-94
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DAVID PAWLACZYK, in a field survey on DECEMBER 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
 N. 36° E. 91 LINKS 24" BLACK OAK
 S. 50° W. 41 LINKS 18" BLACK OAK

Handwritten signature/initials

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD IN PAVEMENT
 PREVIOUS LAND CORNER RECORDATION CERTIFICATES
 LIBER 5892 PAGE 245
 LIBER 6373 PAGE 872
 LIBER 7673 PAGE 256
 LIBER 11062 PAGE 226

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P. A. 345 BRASS
 CAP STAMPED #17632 ON 3/4" x 24" IRON ROD
 ACCESSORIES ESTABLISHED
 N. 30° E., 71.88' ♀ TOP NUT OF FIRE HYDRANT
 S. 30° E., 73.11' WITNESS TAG ON EAST FACE UTILITY POLE
 S. 60° W., 87.78' ♀ TOP NUT OF FIRE HYDRANT
 N. 60° W., 47.12' WITNESS TAG ON SOUTHWEST FACE UTILITY POLE

Signed by *David Pawlaczyk*

Date 1-11-94

Surveyor's Michigan License No. 17632

