

**SURVEY &
REMONUMENTATION**

LIBER **14992** OF **102**

94 254985

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

For corners in

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

OAKLAND
(County)

Located In: AVON
TOWNSHIP Corner Code ##

- 1. Public Land Survey T-3-N R-11-E K-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 22 SEP 94 8:44 A.M. RECEIPT# 338
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK, REGISTER OF DEEDS
 ACT 345, P.A. 1990

APPROVED ON: 1-12-94
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DAVID PAWLACZYK, in a field survey on DECEMBER 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
N. 38° W. 153 LINKS 32" WHITE OAK

Handwritten initials/signature

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND LARGE NAIL IN MONUMENT BOX
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 6877 PAGE 561
LIBER 11062 PAGE 226

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
REPLACED THE LARGE NAIL WITH P. A. 345 BRASS
CAP STAMPED # 17632 ON 3/4" x 24" IRON ROD
ACCESSORIES ESTABLISHED
N. 45° E., 46.54' WITNESS TAG ON SOUTH FACE UTILITY POLE
S. 70° E., 50.20' CUT CROSS NORTH RIM OF SANITARY MANHOLE
S. 45° W., 45.56' WITNESS TAG ON NORTH FACE UTILITY POLE
N. 45° W., 57.19' @ TOP NUT OF FIRE HYDRANT

Signed by [Signature]

Date 17632 1-11-94

Surveyor's Michigan License No. 17632

