

**SURVEY &
REMONUMENTATION**

LIBER **14992** PG **104**

94 254987

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

COMMISSION

OAKLAND
(County)

Located In: AVON
TOWNSHIP

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T-3-N R-11-E | <u>K-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
22 SEP 94 8:44 A.M. RECEIPT# 33B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance With
ACT 345, P.A. 1990

APPROVED ON: 1-12-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID PAWLACZYK, in a field survey on DECEMBER 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
N. 54° W. 12 LINKS 9" RED OAK
S. 71½° E. 10 LINKS 5" BEECH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ½" RE-ROD IN MONUMENT BOX
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 9888 PAGE 264
LIBER 11157 PAGE 092
LIBER 11521 PAGE 121
LIBER 11622 PAGE 375

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE ½" RE-ROD WITH P. A. 345 BRASS
CAP STAMPED # 17632 ON ¾" X 24" IRON ROD.
ACCESSORIES ESTABLISHED
DUE EAST, 22.46' CUT CROSS NORTH RIM SANITARY MANHOLE
S. 20° E., 183.31' WITNESS TAG ON NORTH FACE UTILITY POLE
DUE WEST, 31.03' WITNESS TAG ON SOUTH FACE UTILITY
N. 45° W., 72.84' WITNESS TAG ON NORTHEAST FACE UTILITY POLE

Signed by [Signature] Date 17632 1-11-94
Surveyor's Michigan License No. 17632

