

**SURVEY &  
REMONUMENTATION**

LIBR 14992 PC 106

94 254989

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

OK - T. SMITH

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**COMMISSION**

OAKLAND  
(County)

Located In: AVON TOWNSHIP Corner Code: ##

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
22 SEP 94 8:44 A.M. RECEIPT# 33B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 1-12-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

- |                                    |                              |             |
|------------------------------------|------------------------------|-------------|
| 1. Public Land Survey              | T- <u>3-N</u> R- <u>11-E</u> | <u>K-12</u> |
|                                    | T ___ R ___                  | _____       |
|                                    | T ___ R ___                  | _____       |
|                                    | T ___ R ___                  | _____       |
| 2. Property Controlling in Section | S ___ T ___ R ___            | _____       |
|                                    | S ___ T ___ R ___            | _____       |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___            | _____       |
|                                    | S ___ T ___ R ___            | _____       |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID PAWLACZYK, in a field survey on JANUARY 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES  
N. 17 1/2° E. 11 LINKS 11" WHITE OAK  
S. 02° W. 70 LINKS 12" RED OAK

*Handwritten initials/signature*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PREVIOUS LAND CORNER RECORDATION CERTIFICATES  
NONE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

PLACED P.A. 345 BRASS CAP STAMPED # 17632  
ON 3/4" x 24" IRON ROD IN MONUMENT BOX  
ACCESSORIES ESTABLISHED  
DUE EAST, 26.32' WITNESS TAG ON NORTH FACE 30" OAK  
S. 20° E., 137.74' & TOP NUT OF FIRE HYDRANT  
S. 20° W., 99.53' WITNESS TAG ON NORTHWEST FACE 20" HICKORY  
N. 50° W., 73.16' WITNESS TAG ON NORTHEAST FACE 12" PINE

Signed by [Signature]

Date 1-11-94

Surveyor's Michigan License No. 17632

