

**SURVEY &
REMONUMENTATION**

LIBER 14992 PG 108

94 254991

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OAKLAND
(County)

Located In: AVON TOWNSHIP Corner Code #

OK - T. SMITH

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T-3-N R-11-E | L-7 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
22 SEP 94 8:44 A.M. RECEIPT# 338
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, P.L.S. REGISTER OF DEEDS

APPROVED ON: 172-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID PAWLACZYK, in a field survey on DECEMBER 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
N. 25° W. 31 LINKS 12" WHITE OAK
S. 25° W. 31 LINKS 8" BLACK OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT
PREVIOUS LAND CORNER RECORDATION CERTIFICATE
LIBER 7283 PAGE 216
LIBER 7673 PAGE 256
LIBER 9772 PAGE 741

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED CONCRETE MONUMENT WITH P.A. 345 BRASS
CAP STAMPED #17632 ON CONCRETE MONUMENT
ACCESSORIES ESTABLISHED
N. 20° E., 107.80' WITNESS TAG ON SOUTHEAST FACE 30" BLACK WALNUT
S. 60° E., 48.06' WITNESS TAG ON NORTH FACE 16" BLACK WALNUT
DUE SOUTH, 9.18' WITNESS TAG ON WEST FACE 14" OAK
S. 45° W., 12.35' WITNESS TAG ON EAST FACE 28" BLACK WALNUT

Signed by [Signature]

Date 1-11-90

Surveyor's Michigan License No. 17632

