

**SURVEY &  
REMONUMENTATION**

LIBER **14992** PC **109**

94 **254992**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

**COMMISSION** Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

OAKLAND  
(County)

Located In: AVON  
TOWNSHIP Corner Code #

- |                                    |                              |            |
|------------------------------------|------------------------------|------------|
| 1. Public Land Survey              | T- <u>3-N</u> R- <u>11-E</u> | <u>L-9</u> |
|                                    | T _____ R _____              | _____      |
|                                    | T _____ R _____              | _____      |
|                                    | T _____ R _____              | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____      | _____      |
|                                    | S _____ T _____ R _____      | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____      | _____      |
|                                    | S _____ T _____ R _____      | _____      |

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
22 SEP 94 8:45 A.M. RECEIPT# 33B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. CALLEN/REGISTER OF DEEDS  
ACT 345, P.A. 1990

APPROVED ON: 1-12-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID PAWLACZYK, in a field survey on DECEMBER 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

*POST WAS SET PER GOVERNMENT LAND OFFICE NOTES  
S. 61°E. 13 LINKS 24" WHITE OAK  
N. 28°W. 30 LINKS 8" BLACK OAK*

*760  
360  
File*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

*FOUND 1/2" RE-ROD IN MONUMENT BOX  
PREVIOUS LAND CORNER RECORDATION CERTIFICATES  
LIBER 6877 PAGE 557  
LIBER 11157 PAGE 092  
LIBER 12236 PAGE 227*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

*REPLACED THE 1/2" RE-ROD WITH P.A. 345 BRASS  
CAP STAMPED #17632 ON 3/4" X 24" IRON ROD.  
ACCESSORIES ESTABLISHED  
N. 45°E., 61.17' SOUTHWEST CORNER HOUSE # 1575  
S. 70°E., 118.39' @ TOP NUT OF FIRE HYDRANT  
DUE SOUTH, 45.03' WITNESS TAG WEST FACE UTILITY POLE  
DUE NORTH, 61.17' WITNESS TAG ON WEST FACE UTILITY POLE*

Signed by *[Signature]*

Date 1-11-94

Surveyor's Michigan License No. 17632

