

**SURVEY & REMONUMENTATION**

94 254993

MAY - 1 1995

LIBER 14992 PC 110

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OK - T. SMITH

OAKLAND  
(County)

Located In: AVON TOWNSHIP Corner Code ##

- |                                    |                              |             |
|------------------------------------|------------------------------|-------------|
| 1. Public Land Survey              | T- <u>3-N</u> R- <u>11-E</u> | <u>L-11</u> |
|                                    | T _____ R _____              | _____       |
|                                    | T _____ R _____              | _____       |
|                                    | T _____ R _____              | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____      | _____       |
|                                    | S _____ T _____ R _____      | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____      | _____       |
|                                    | S _____ T _____ R _____      | _____       |

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
22 SEP 94 8:45 A.M. RECEIPT# 338  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 1-12-94  
OAKLAND COUNTY REMONUMENTATION  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID PAWLACZYK, in a field survey on DECEMBER 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES  
S, 37° E. 146 LINKS 36" BLACK OAK

*Handwritten initials/signature*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

RE-ESTABLISHED CORNER FROM EXISTING WITNESSES  
PREVIOUS LAND CORNER RECORDATION CERTIFICATES  
LIBER 5902 PAGE 284  
LIBER 11521 PAGE 121

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET P.A. 345 BRASS CAP STAMPED # 17632  
ON 3/4" x 24" IRON ROD.  
ACCESSORIES ESTABLISHED  
N. 30° E., 69.36' WITNESS TAG ON WEST FACE UTILITY POLE  
S. 36° E., 53.58' WITNESS TAG ON NORTHEAST FACE UTILITY POLE  
S. 21° W., 50.04' WITNESS TAG ON NORTH FACE UTILITY POLE  
N. 60° W., 108.46' WITNESS TAG ON EAST FACE 22" ELM

igned by [Signature] Date 1-11-94

urveyor's Michigan License No. 17632

