

**SURVEY & REMONUMENTATION**

LIBER **14992** PG. **112**

94 **254995**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

OK - T. SMITH

OAKLAND  
(County)

Located In: AVON TOWNSHIP Corner Code #

- 1. Public Land Survey T-3-N R-11-E M-7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

\$ 7.00 MISCELLANEOUS RECORDING  
 \$ 2.00 REMONUMENTATION  
 22 SEP 94 8:45 A.M. RECEIPT# 338  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK REGISTER OF DEEDS  
 ACT 345, P.A. 1990

APPROVED ON: 1-12-94  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

I, DAVID PAWLACZYK, in a field survey on NOVEMBER 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
POST WAS SET PER GOVERNMENT LAND OFFICE NOTES  
N. 31° E. 31 LINKS 14" THORNBUSH  
S. 01° E. 23 LINKS 16" HICKORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1/2" RE-ROD IN MONUMENT BOX  
PREVIOUS LAND CORNER RECORDATION CERTIFICATES  
LIBER 9772 PAGE 742

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
REPLACED THE 1/2" RE-ROD WITH P.A. 345 BRASS  
CAP STAMPED #17632 ON 3/4" x 24" IRON ROD.  
ACCESSORIES ESTABLISHED  
N. 30° E., 43.08' WITNESS TAG ON SOUTH FACE UTILITY POLE  
DUE EAST, 46.62' WITNESS TAG ON NORTH FACE 10" ASH  
DUE WEST, 33.30' CONCRETE MONUMENT  
N. 15° W., 37.83' WITNESS TAG ON EAST FACE 28" ASH

Signed by [Signature]  
 Surveyor's Michigan License No. 17632

Date 1-11-94

