

SURVEY &
REMONUMENTATION

94 254996

LIBER 14992 PG 113

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

OK - T. SMITH

OAKLAND (County) Located In: AVON TOWNSHIP Corner Code #

- 1. Public Land Survey T-3-N R-11-E M-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 22 SEP 94 8:45 A.M. RECEIPT# 338
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
 ACT 345, P.A. 1990

APPROVED ON: 1-12-94
 OAKLAND COUNTY REMONUMENTATION
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID PAWLACZYK, in a field survey on NOVEMBER 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

*POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
 S. 47° W. 46 LINKS 16" WHITE OAK
 N. 41° W. 34 LINKS 11" BLACK OAK*

17632

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

*FOUND 1" IRON ROD IN MONUMENT BOX
 PREVIOUS LAND CORNER RECORDATION CERTIFICATES
 LIBER 6451 PAGE 133
 LIBER 6926 PAGE 426
 LIBER 8637 PAGE 44*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

*REPLACED THE 1" IRON ROD WITH P.A. 345 BRASS
 CAP STAMPED #17632 ON 3/4" x 24" IRON ROD.
 ACCESSORIES ESTABLISHED
 N. 30° E., 47.31' WITNESS TAG ON NORTH FACE UTILITY POLE
 S. 20° E., 72.36' WITNESS TAG ON WEST FACE UTILITY POLE
 S. 30° W., 74.28' WITNESS TAG ON NORTHWEST FACE 4" ELM
 N. 45° W., 63.69' WITNESS TAG ON SOUTH FACE 12" LOCUST*

Signed by [Signature] Date 1-11-94
 Surveyor's Michigan License No. 17632

