

**SURVEY & REMONUMENTATION**

LIBER **14992** PG **115**

94 **254998**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

OAKLAND COMMISSION  
(County)

Located In: AVON TOWNSHIP Corner Code #

- |                                    |                            |             |
|------------------------------------|----------------------------|-------------|
| 1. Public Land Survey              | T <u>3-N</u> R <u>11-E</u> | <u>M-10</u> |
|                                    | T ___ R ___                | _____       |
|                                    | T ___ R ___                | _____       |
|                                    | T ___ R ___                | _____       |
| 2. Property Controlling in Section | S ___ T ___ R ___          | _____       |
|                                    | S ___ T ___ R ___          | _____       |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___          | _____       |
|                                    | S ___ T ___ R ___          | _____       |

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
22 SEP 94 8:45 A.M. RECEIPT# 338  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 1-12-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DAVID PAWLACZYK, in a field survey on NOVEMBER 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

*POST WAS SET PER GOVERNMENT LAND OFFICE NOTES  
S. 72° W. 38 LINKS 9" WHITE OAK  
S. 78° E. 56 LINKS 18" BLACK OAK*

*Handwritten initials/signature*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

*FOUND 1/2" RE-ROD IN MONUMENT BOX  
PREVIOUS LAND CORNER RECORDATION CERTIFICATES  
LIBER 11157 PAGE 091*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

*REPLACED 1/2" RE-ROD WITH P.A. 345 BRASS  
CAP STAMPED # 17632 ON 3/4" x 24" IRON ROD  
ACCESSORIES ESTABLISHED  
N. 60° E., 35.17' WITNESS TAG ON SOUTH FACE UTILITY POLE  
S. 70° E., 89.36' NORTHWEST CORNER HOUSE  
S. 30° E., 97.31' WITNESS TAG ON EAST FACE 12" BOX ELDER  
N. 45° W., 39.42' @ TOP NUT OF FIRE HYDRANT*

Signed by [Signature]  
Surveyor's Michigan License No. 17632

Date 1-11-94

