

SURVEY &
REMONUMENTATION

LIBER 14992 PG 116

94 254999

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in **COMMISSION**

OAKLAND
(County)

Located In: AVON
TOWNSHIP Corner Code #

- | | | | |
|---------------------------------------|---------------|----------------|-------------|
| 1. Public Land Survey | T- <u>3-N</u> | R- <u>11-E</u> | <u>M-11</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 4. Lot No. _____, Recorded Plat _____ | | | |
| 5. Private Claims _____ | | | |

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
22 SEP 94 8:45 A.M. RECEIPT# 338
PAID RECORDED - OAKLAND COUNTY
LYNN D. ACTON, PLAT # 17632 REGISTER OF DEEDS

APPROVED ON: 1-12-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID PAWLACZYK, in a field survey on DECEMBER 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES
N. 7 1/2° E, 40 LINKS 18" WHITE OAK
S. 86° W 75' LINKS 19" RED OAK

*700
700
File*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PREVIOUS LAND CORNER RECORDATION CERTIFICATES
NONE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

PLACED P. A. 345 BRASS CAP STAMPED # 17632
ON 3/4" X 24" IRON ROD IN MONUMENT BOX
ACCESSORIES ESTABLISHED
N. 65° E., 98.13' @ TOP NUT OF FIRE HYDRANT
S. 40° E., 71.18' WITNESS TAG ON NORTHEAST FACE 12" OAK
S. 40° W., 63.05' WITNESS TAG ON NORTHEAST FACE GUY POLE
N. 40° W. 74.68' @ GATE VALVE & WELL

Signed by [Signature]

Date 1-11-94

Surveyor's Michigan License No. 17632

