

**SURVEY & REMONUMENTATION**

MAY 24 2000

LIBER 20657 - 282

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

374923

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	A-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T	R
	S T	R
3. Miscellaneous Property in Sec.	S T	R
	S T	R

LIBER 20657 PAGE 282  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
10/12/1999 08:06:33 A.M. RECEIPT# 88906  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 9-22-99 JK  
OAKLAND COUNTY REMONUMENTATION  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on February 28, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There is one LCRC recorded at Oakland County; McGinnis 1992.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a nail set in concrete post at this location. Validated location with monumentation recovered along north and east of Section 6 per Anderson's 1978 survey. This corner is common to M-1 of T4N., R6E., Tyrone Township, Livingston County.

\*Recovered Witnesses:

- N 06°E 61.80' nail with washer in west side twin 10" Oak.
- \*N 06°E 61.25' nail with tag #32332 in west side twin Oak.
- \*N 78°W 25.61' nail with tag #32332 in north side power pole.
- N 78°W 25.61' nail with washer in north side power pole.
- S 64°E 52.45' nail in north side 12" dead tree.
- \*S 52°E 41.49' nail with tag.
- \*S 80°E 159.39' nail in north side 42" Oak.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 in concrete post with concrete nail.

Set Witnesses:

- \*N 06°E 61.80' Mag nail with OCRT #24598 in west side twin 10" Oak.
- \*N 78°W 25.61' Mag nail with OCRT #24598 in north side power pole.
- \*S 52°E 41.49' Mag nail with OCRT #24598 in north side 12" Elm.
- \*S 80°E 159.35' Mag nail with OCRT #24598 in north side 42" Oak.

\*Reused Recovered Witnesses

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Joseph C. Kapelczak Date 9/21/99

Surveyor's Michigan License No. 24598

