

MAY 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

127802

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T <u>4N</u> R <u>7E</u>	<u>A-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 21403 PAGE 383
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 05/19/2000 10:35:43 A.M. RECEIPT# 36329
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 7-7-99 JS
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on April 15, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monumentation was recovered at this location. This corner was re-established by placing the monument on the east line of T. 4N R. 6E, Tyrone Township, Livingston County equidistant between A-11 and A-13, T. 4N, R 7E, Rose Township.

Recovered Witnesses:

S 11°W 35.91' 20 Penny nail east side 16" Poplar.
 S 78°E 17.82' found 20 Penny nail west side 14" Oak.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron with Oakland County Remonumentation Brass Cap stamped #24598 in gravel road.

Set Witnesses:

N 34°W 31.89' Mag nail with OCRT #24598 west side 18" Oak.
 S 75°W 26.12' Mag nail with OCRT #24598 south side triple 8" Hickory.
 S 11°W 35.91' Mag nail with OCRT #24598 east side 16" Poplar.
 S 78°E 18.64' Mag nail with OCRT #24598 south side 14" Oak.
 A-12 to M-12 T 4N., R 6E Tyrone Township, Livingston County N 03°13'26"W 33.71'

ZP
R



Signed by Joseph C. Kapelczak
 Surveyor's Michigan License No. 24598

Date 5/18/2000