

MAY 24 2000

LIBER 20657 - 298

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

374931

For corners in

<u>Oakland</u> (county)	Located in:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	B-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___	_____
	S___ T___	_____
3. Miscellaneous Property in Sec.	S___ T___	_____
	S___ T___	_____

LIBER 20657 PAGE 298  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
10/12/1999 08:06:33 A.M. RECEIPT# 88906  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 6-16-99 JS  
OAKLAND COUNTY REMONUMENTATION  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on March 17, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered an iron with cap #10057 at this location. Validated location with monumentation recovered from a Tri-County Survey L 9614 P 681 in Section 30.

Recovered Witnesses: Per recorded survey L 9614 P 681

N 50°W 4.49' nail east side 10" Hickory.  
N 70°E 15.56' nail south side 12" Elm.  
S 15°E 13.86' nail east side 20" Oak.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 with concrete monument.

Set Witnesses:

S 50°W 32.07' nail with OCRT #24598 southeast side Twin 18" Oak.  
N 50°W 4.49' OCRT #24598 and Mag nail east side 10" Hickory.  
N 70°East 15.56' OCRT #24598 and Mag nail south side 12" Elm.  
S 15°E 13.86' OCRT #24598 and Mag nail east side 20" Oak.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	14	15	16	17	18	19	20	21	22	23	24	25	26
5													
6	27	28	29	30	31	32	33	34	35	36	37	38	39
7													
8	40	41	42	43	44	45	46	47	48	49	50	51	52
9													
10	53	54	55	56	57	58	59	60	61	62	63	64	65
11													
12	66	67	68	69	70	71	72	73	74	75	76	77	78
13													



Signed by Joseph C. Kapelczak

Date 6/16/99

Surveyor's Michigan License No. 24598