

MAY 24 2000

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	C-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 03/01/1999 02:59:15 P.M. RECEIPT# 4397
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CABBELL, CLERK/REGISTER OF DEEDS

HR-199068463

Compliance with ACT 345, P.A. 1990

APPROVED ON: 2-3-99 53
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on March 10, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There are two LCRC's recorded at Oakland County; Albright 1971 and Bonno 1992.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a "T" iron at this location. The T-iron was recovered as per LCRC L.13268 P. 101 with the recovered witnesses. The corner was also validated with irons found on the south side of Baker Road west of the corner and monumentation found on the east side of Hickory Ridge Road between C-3 and C-4.

Recovered Witnesses:

- *N 35°E 23.45' nail with tag #32332 in top of guard rail post.
- N 39°E 23.54' nail with tag #10097 in top of guard rail post.
- *S 47°E 29.67' nail with tag #32332 in top of guard rail post.
- S 47°E 29.55' nail with Delta tag in top of guard rail post.
- *S 33°W 28.28' nail with tag #32332 in top of guard rail post.
- S 33°W 28.34' nail with tag #10057 in top of guard rail post.
- *N 68°W 24.46' nail with tag #32332 in top of guard rail post.
- N 68°W 24.30' nail with Delta tag in top of guard rail post.

900 FILE
200

2/22

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 with 5/8" iron rod.

Set Witnesses:

- *N 35°E 23.45' Mag nail with OCRT in guard rail post.
- *S 47°E 29.69' Mag nail with OCRT in guard rail post.
- *S 33°W 28.31' Mag nail with OCRT in guard rail post.
- *N 68°W 24.46' Mag nail with OCRT in guard rail post.

*Reused Recovered Witnesses

Signed by Joseph C. Kapelczak

Date 2/5/99

Surveyor's Michigan License No. 24598

