

**SURVEY & REMONUMENTATION**

MAY 24 2000

LIBER 19843PC643

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Oakland</u> (county)	Located In: <u>Rose Township</u>	Corner Code #
1. Public Land Survey	<u>T4N R7E</u>	<u>C-5</u>
	T <u>    </u> R <u>    </u>	
	T <u>    </u> R <u>    </u>	
	T <u>    </u> R <u>    </u>	
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	

131644

LIBER 19843 PAGE 643  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
04/16/1999 08:59:49 A.M. RECEIPT# 19968  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 3-3-99 JS  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on March 17, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		22
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There are two LCRC's recorded at Oakland County; Anderson 1978 and Ward 1989.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 5/8" iron in monument box in Hickory Ridge Road at Sackner Road at this location. This location was validated with monumentation recovered for McClatchey's Taylor Lake Heights Subdivision.

Recovered Witnesses

- S 62°W 64.05' double-headed nail with RCOC tag north side 18" Walnut.
- S 62°W 63.50' nail with Delta Tag north side 18" Walnut.
- S 62°W 63.20' nail with tag #32332 north side 18" Walnut.
- S 23°W 72.16' nail with Delta tag east face 18" Walnut.
- S 23°W 72.16' nail with tag #32332 east face 18" Walnut.
- N 85°E 30.73' nail with "Survey Point" tag north side 26" Maple.
- N 85°E 30.64' nail with tag #32332 north side 26" Maple.
- \*N 45°E 44.70' nail with Grant Ward tag west side 18" Maple.

JP  
R

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 in existing monument box.

Set Witnesses:

- \*N 45°E 44.70' Mag nail with OCRT west side 18" Maple.
- N 85°E 30.73' Mag nail with OCRT north side 26" Maple.
- S 17°E 99.91' Mag nail with OCRT west side 30" Maple.
- S 62°W 63.20' Mag nail with OCRT north side 18" Walnut.



\*Reused Recovered Witness

Signed by Joseph C. Kapelczak Date 2/22/99

Surveyor's Michigan License No. 24598