

MAY 24 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

374937

SECTION

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	C-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

LIBER 20657 PAGE 310  
 \$9.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 10/12/1999 08:06:33 A.M. RECEIPT# 88906  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 6-16-99 JS  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on April 9, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2											
3											
4											
5											
6											
7											
8											
9											
10											
11											
12											
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
 There are two LRC's recorded at Oakland County; Albright 1977 and Ward 1988.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron in monument box in Hickory Ridge Road at this location. Validated location with monumentation recovered along the west R.O.W. of Hickory Ridge Road north of corner along with witnesses recovered in the above referenced LCRC's.

Recovered Witnesses:

S 83°E 33.21' PK nail with Ward tag south side 8" Locust.  
 S 83°E 33.21' nail with #32332 tag south side 8" Locust.  
 N 56°W 39.45' nail with Ward tag northeast side 18" Locust.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 on existing iron.

Set Witnesses:

\*S 83°E 33.21' Mag nail with OCRT #24598 south side 8" Locust.  
 S 34°W 64.05' Mag nail with OCRT #24598 southeast side 38" Oak.  
 S 39°E 62.06' Mag nail with OCRT #24598 southwest side 8" Elm.  
 N 56°W 39.45' Mag nail with OCRT #24598 with OCRT #24598 northeast side 18" Locust.

\*Reused Recovery Witness



Signed by Joseph C. Kapelczak

Date 6/16/99

Surveyor's Michigan License No. 24598