

MAY 24 2000

LIBER 20657 312

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

374938

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	D-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 20657 PAGE 312  
 \$9.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 10/12/1999 08:06:33 A.M. RECEIPT# 88906  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 9-22-99  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on March 10, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
 There are two LCRC's recorded at Oakland County; Ward 1994 and Albright 1978.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron 0.03' south of the township line 183.81' west of D-13 Holly Township. Validated the location of the corner with monumentation found on the south R.O.W. line of Houser Road immediately south and east of the corner. All four witnesses of L 15193 P 690 and P 691 by Ward were recovered and agree with the location of this corner.

Recovered Witnesses:

- \*N 65°W 28.13' PK nail with Grant Ward tag in side of 12" Elm.
- \*S 52°W 28.16' PK nail with Grant Ward tag in side of 8" Locust.
- \*S 05°W 16.20' PK nail with Grant Ward tag in side 10" Cherry.
- \*S 61°E 35.85' PK anil with Grant Ward tag in side of 12" Poplar.
- S 61°E 35.93' nail with Delta Tag in side of 12" Poplar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron rod with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- \*N 65°W 28.13' Mag nail with OCRT #24598 in side of 12" Elm.
- \*S 52°W 28.16' Mag nail with OCRT #24598 in side of 8" Locust.
- \*S 05°W 16.20' Mag nail with OCRT #24598 in side of 10" Cherry.
- \*S 61°W 35.85' Mag nail with OCRT #24598 in side of 12" Poplar.

\*Reused Recovered Witnesses



Signed by Joseph C. Kapelczak Date 9/22/99

Surveyor's Michigan License No. 24598