

MAY 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

131659

For corners in

<u>Oakland</u> (county)	Located in: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	E-2
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

LIBER 19843 PAGE 673
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 04/16/1999 08:59:50 A.M. RECEIPT# 19968
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 4-07-99 JS
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on March 10, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There are two LCRC's recorded at Oakland County; Stonerock 1972, 1/2" iron and Stonerock 1973, 1/2" iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered an empty monument box and a PK nail at this location. Validated PK nail as the corner location with monumentation recovered on the east R.O.W. line of Fish Lake Road north of the Section Corner.

Recovered Witnesses

- N 42°E 61.82' PK nail with Grant Ward tag south side power pole.
- *N 42°E 62.02' Double Headed nail with OCRC tag south side power pole.
- S 58°W 64.99' PK nail with Grant Ward washer northwest side power pole.
- N 44°W 71.69' PK nail with Grant Ward washer east side 24" Willow.

*2p
R*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron with Oakland County Remonumentation Brass Cap stamped #24598 in new monument box.

Set Witnesses:

- *N 42°E 61.82' Mag nail with OCRT #24598 south side power pole.
- S 21°E 89.37' Mag nail with OCRT #24598 west side fence post.
- *S 58°W 64.99' Mag nail with OCRT #24598 northwest side power pole.
- *N 44°W 71.69' Mag nail with OCRT #24598 east side 24" Willow.

*Reused Recovered Witness



Signed by Joseph C. Kapelczak
 Surveyor's Michigan License No. 24598

Date 4/6/99