

MAY 24 2000

LIBER 19842PG633

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (county)	Located In: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	E-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

131638

LIBER 19843 PAGE 633
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 04/16/1999 08:59:10 A.M. RECEIPT# 1999
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF I
 Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 3-3-99 JS
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on March 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Set post in 1816 G.L.O. Survey.
 There is one LCRC recorded at Oakland County; Hart 1995.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Recovered a 1/2" iron in Fish Lake Road at this location. This location was validated with monumentation recovered from recorded survey of Section 9, Newman 1997, L 17105 P 611, and the R.O.W. on the east side of Fish Lake Road south of the corner.

2P
R

- Recovered Witnesses:
- *Due East 21.01' nail southwest side 40" Oak.
 - *N 40°W 29.92' nail in northeast side 12" Walnut.
 - *N 40°E 35.62' nail northwest side 16" Walnut.
 - *S 20°W 44.43' nail southeast side 14" Walnut.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Oakland County Remonumentation Brass Cap stamped #24598 in gravel road.

- Set Witnesses:
- *Due East 21.01' nail with OCRT #24598 southwest side 40" Oak.
 - *N 40°W 29.92' nail with OCRT #24598 northeast side 12" Walnut.
 - *N 40°E 35.62' nail with OCRT #24598 northwest side 16" Walnut.
 - *S 20°W 44.43' nail with OCRT #24598 southeast side 14" Walnut.

*Reused Recovered Witness



Signed by Joseph C. Kapelczak Date 2/22/99
 Surveyor's Michigan License No. 24598