

MAY 24 2000

SECTION

LIBER 20657 PAGE 322
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

374943

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	E-7
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___	_____
	S___ T___	_____
3. Miscellaneous Property in Sec.	S___ T___	_____
	S___ T___	_____

LIBER 20657 PAGE 322
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
10/12/1999 08:06:33 A.M. RECEIPT# 88906
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 4-21-99 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

I, Joseph C. Kapeiczak, in a field survey on October 7, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There is one LCRC recorded at Oakland County; Ward 1993.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron in Fish Lake Road at this location. This location was validated with monumentation recovered along the R.O.W. of Fish Lake Road south of section corner and recovered witnesses in the recorded LCRC's.

*Recovered Witnesses:

- *N 31°E 57.30' nail west side power pole.
- N 31°E 57.30' nail with Oakland County Road Commission tag west side power pole.
- *S 65°E 64.14' nail north side 14" Oak.
- S 17°W 47.06' nail east side power pole.
- N 24°W 59.84' nail northeast side power pole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron with Oakland County Remonumentation Brass Cap stamped #24598 in gravel road.

Set Witnesses:

- *N 31°E 57.13' Mag nail with OCRT #24598 east side power pole.
- *S 65°E 64.14' OCRT #24598 and Mag nail north side 14" Oak.
- *S 17°W 47.06' OCRT #24598 and Mag nail east side power pole.
- *N 24°W 59.84' OCRT #24598 and Mag nail northeast side power pole.

*Reused Recovered Witnesses



Signed by Joseph C. Kapeiczak

Date 4/20/99

Surveyor's Michigan License No. 24598