

MAY 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

374946

For corners in

Oakland (county)	Located In: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	E-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 20657 PAGE 328
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 10/12/1999 08:06:33 A.M. RECEIPT# 88906
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEED

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 5-26-99 JS
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on April 13, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There are two LCRC's recorded at Oakland County; Anderson 1977 and Bonno 1992.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1" pipe in Fish Lake Road at this location. This location was validated with monumentation recovered along the R.O.W. of Fish Lake Road along with witnesses from the above referenced LCRC's.

Recovered Witnesses:

- *N 32°W 48.38' nail with Bonno Tag #32332 east side 8" Oak.
- *N 80°W 27.63' nail with Bonno Tag #32332 south side twin 28" Cherry.
- S 17°W 71.58' nail with Bonno Tag #32332 east side twin 18" Bass Wood.
- *S 80°E 28.30' nail with Bonno Tag #32332 north side 48" Oak.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron rod with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- N 32°W 40.39' Mag nail with OCRT #24598 east side 8" Oak.
- *S 80°E 28.30' Mag nail with OCRT #24598 north side 48" Oak.
- S 17°W 71.83' Mag nail with OCRT #24598 west side twin 18" Bass Wood.
- *N 80°W 27.63' Mag nail with OCRT #24598 south side twin 28" Cherry.

*Reused Recovered Witnesses

	A	B	C	D	E	F	G	H	I	J	K	L
2	0		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		18		19		20		21	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												



Signed by

Joseph C. Kapelczak

Date

5/26/99

Surveyor's Michigan License No. 24598