

MAY 24 2000

20657 330

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

374947

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	E-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___	R___
	S___ T___	R___
3. Miscellaneous Property in Sec.	S___ T___	R___
	S___ T___	R___

LIBER 20657 PAGE 330
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 10/12/1999 08:06:33 A.M. RECEIPT# 88906
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 7-7-99 SK
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on April 14, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	15		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There are two LCRC's recorded at Oakland County; Albright 174 and Bonno 1992.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a large rock in Fish Lake Road at this location. Re-established corner location on rock with recovered witnesses from LCRC's L 6373 P 862 and L15270 P 637. This location was validated with monumentation recovered along the R.O.W. of Fish Lake Road south of the corner.

Recovered Witnesses:

- *N 30°E 39.98' nail with tag #32332 northwest side 16" Hickory.
- *N 30°E 39.48' nail southeast side 16" Hickory.
- *N 77°E 30.87' nail north side 24" Oak.
- *S 75°E 29.93' nail with tag #32332 south side 16" Oak.
- S 45°E 43.89' mini PK nail northeast 16" Hickory.
- *S 45°E 43.45' nail west side 16" Hickory.
- *S 60°W 44.23' nail with tag #32332 south side quad 8" Cherry.

29
R

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/8" hole drilled with chiseled "+" in top of large rock.

Set Witnesses:

- *N 77°E 30.87' Mag nail with OCRT #24598 north side 24" Oak.
- *S 45°E 43.89' Mag nail with OCRT #24598 northeast side 16" Hickory.
- *N 30°E 39.95' Mag nail with OCRT #24598 northwest side 16" Hickory.
- *S 60°W 44.23 Mag nail with OCRT #24598 south side quad 8" Cherry.

*Reused Recovered Witnesses

Signed by Joseph C. Kapelczak

Date 6/26/99

Surveyor's Michigan License No. 24598

