

MAY 24 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

374948

SECTION

For corners in

Oakland (county)	Located In: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	E-12
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___	R___
	S___ T___	R___
3. Miscellaneous Property in Sec.	S___ T___	R___
	S___ T___	R___

LIBER 20657 PAGE 332  
 \$9.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 10/12/1999 08:06:33 A.M. RECEIPT# 88906  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 8-17-99 JH  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on April 14, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
 There are two LCRC's recorded at Oakland County; Albright 1974 and Bonno 1990.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a square boat spike at this location. This location was validated with monumentation recovered along the west R.O.W. of Fish Lake Road south of the corner. One witness was recovered from the Bonno LCRC of 1990.

Recovered Witnesses:

- N 30°W 44.74' nail east side 18" Oak.
- N 70°W 20.87' nail south side 18" Ash.
- \*N 90°W 29.36' nail north side 8" Maple.
- S 20°W 60.68' nail with tag #32332 east side 18" Oak.
- \*S 45°E 37.51' nail with tag #32332 northeast side 18" Hickory.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- N 30°W 44.74' Mag nail with OCRT #24598 east side 18" Oak.
- N 70°W 20.87' Mag nail with OCRT #24598 south side 18" Ash.
- S 20°W 60.68' Mag nail with OCRT #24598 east side 18" Oak.
- \*S 45°E 37.51' Mag nail with OCRT #24598 northeast side 18" Hickory.

\*Re-used recovered witnesses.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		28		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Signed by Joseph C. Kapelczak  
 Surveyor's Michigan License No. 24598

Date 8/3/99

