

MAY 24 2000

LIBER 20657 - 334

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

374949

SECTION  
For corners in

Oakland (county)	Located in: Rose Township	Comer Code #
1. Public Land Survey	T4N R7E	F-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 20657 PAGE 334  
 \$9.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 10/12/1999 08:06:33 A.M. RECEIPT# 88906  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 9-22-99 JH  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on March 6, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2												
3												
4												
5												
6	16	17	18	19	20	21	22	23	24	25	26	27
7												
8	19	20	21	22	23	24	25	26	27	28	29	30
9												
10	30	31	32	33	34	35	36	37	38	39	40	41
11												
12	31	32	33	34	35	36	37	38	39	40	41	42
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
 There is one LCRC recorded at Oakland County; Albright 1976.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 2" pipe 0.10' north of the township line and 70.58' west of F-13 Holly Township This location was validated with monumentation recovered along Houser Road east of the corner and the south line of T5N., R7E., Holly, Township.

Recovered Witnesses:

- \*Due South 19.42' nail with tag #10057/24607 in west side 8" Elm.
- \*S 75°W 21.69' nail with tag #10057/24607 in south side 7" Elm.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- \*Due South 19.42' Mag nail with OCRT #24598 in west side 8" Elm.
- \*S 75°W 21.69' Mag nail with OCRT #24598 in south side 7" Elm.
- N 85°E 4.81' Mag nail with OCRT #24598 north side 5" Elm.
- S 80°E 15.75' Mag nail with OCRT #24598 in north side 8" Elm.

\*Reused Recovered Witnesses



Signed by

*Joseph C. Kapelczak*

Date

9/22/99

Surveyor's Michigan License No. 24598