

MAY 24 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

131635

For corners in

<u>Oakland</u> (county)	Located In: Rose Township	Corner Code # G-4
1. Public Land Survey	T4N R7E	G-4
	T R	
	T R	
	T R	
2. Property Controlling S in Section	T R	
	T R	
3. Miscellaneous S Property in Sec.	T R	
	T R	

LIBER 19843 PAGE 627  
 \$9.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 04/16/1999 08:59:10 A.M. RECEIPT# 19968  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 3-3-99 JS  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on March 2, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	8	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
 There are three LCRC's recorded at Oakland County; Albright 1973, 1/2" iron, Stonerock 1973, iron, and Ward 1982, iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron at this location. This location was validated with distances between Section Corners from record surveys L 7593 P 326 Smith and L 11512 P 220 Ward.

Recovered Witnesses

West 15.31' PK nail with Grant Ward tag south side 10" Maple.  
 S 55°W 2.76' PK nail with Grant Ward tag south side 6" Elm.  
 \*North 9.70' 2 - PK nail and nail - both with Grant Ward tags west side 10" Hickory.  
 N 75°E 20.67' nail with Grant Ward tag south side 12" Elm.  
 N 75°E 20.65' nail south side 12" Elm.  
 West 15.40' nail north side 10" Maple.

2P  
R

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 on concrete monument.

Set Witnesses:

West 15.31' OCRT #24598 Mag nail south side 10" Maple.  
 \*North 9.70' OCRT #24598 Mag nail west side 10" Hickory.  
 N 75°E 20.67' OCRT #24598 Mag nail south side 12" Elm.  
 S 55°W 2.76' OCRT #24598 Mag nail south side 6" Elm.

\*Reused Recovered Witness



Signed by Joseph C. Kapelczak

Date 2/26/99

Surveyor's Michigan License No. 24598