

MAY 24 2000

LIBER 19843 PG 629

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Oakland</u> (county)	Located in:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	G-5
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

131636

LIBER 19843 PAGE 629  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
04/16/1999 08:59:10 A.M. RECEIPT# 19  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 3-3-99 JJ  
OAKLAND COUNTY REMONUMENTATIO.  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	16	17	18	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

I, Joseph C. Kapelczak, in a field survey on March 4, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There are three LCRC's recorded at Oakland County; Heil 1973, Ward 1982 and Bonno 1988.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron in Davisburg Road at this location. This location was validated with monumentation recovered along the R.O.W. line of Davisburg Road and the Grant Ward survey of 1982.

Recovered Witnesses:

- S 40°E 45.75' nail with illegible tag northeast side 30" Maple.
- \*N 07°W 16.26' nail with Grant Ward tag in west side stump.
- \*N 41°W 29.38' nail with Tri-County washer east side 24" dead Oak.
- \*N 41°W 29.67' nail with tag #24607 east side 24" dead Oak.
- \*S 10°W 13.24' nail with illegible tag.

2P  
R

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" bar with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- S 40°E 49.75' Mag nail with OCRT #24598 northeast side 30" Maple.
- N 12°E 33.83' Mag nail with OCRT #24598 east side 18" Oak.
- N 80°W 52.82' Mag nail with OCRT #24598 southwest side 9" Oak.
- S 64°W 56.00' Mag nail with OCRT #24598 north side 8" Cherry.

\*Reused Recovered Witness



Signed by Joseph C. Kapelczak

Date 2/26/99

Surveyor's Michigan License No. 24598